

Piketi	Zemes virsas atzīme m absol.	Pastāvīvošā dibena atzīme m absol.	Projektētā dibena atzīme m absol.	Astātums starp piketiem m	Izrokamais šķērsgrēzums m ²	Vidējais izrokamais šķērsgrēzums m ²	Izrokamā kubatūra m ³	Piezīmes
1	2	3	4	5	6	7	8	9

ŪSIK kods 43193:01

0/00	82.06	82.06	82.06	100.00	0	1.6	160	
01/00	84.43	83.6	82.66	100.00	3.2	5.49	549	
02/00	86.17	84.05	83.27	100.00	7.78	5.995	599,5	
03/00	86.05	84.73	83.83	100.00	4.21	3.815	381,5	
04/00	86.35	85	84.30	100.00	3.42	3.66	366	
05/00	86.70	85.41	84.55	100.00	3.9	3.33	333	
06/00	86.15	85.68	84.79	100.00	2.76	2.44	244	
07/00	86.10	85.85	85.04	100.00	2.12	2.37	237	
08/00	86.73	86.03	85.28	100.00	2.62	2.06	206	
09/00	87.08	86.20	85.75	65.00	1.5	1.4	91	
09/65	87.28	86.32	85.98	45.00	1.3	0.65	29,25	Roku darbs 09/65- 10/45 80m Latvenego, LVRTC. AXXPK kabeļi Caurteka 10/10-10/45
10/10	87.51	86.41	86.02	35.00	0	0	0	
10/45	88.88	86.85	86.38	27.00	0	0.905	24,435	
10/72	88.25	86.86	86.43	17.00	1.81	1.4	23.8	Roku darbs 10/89-

10/89	87,74	86,89	86,46	11,00	0,99	1,085	11,935	11/49 elektrovādi 3v
11/00	87,50	86,91	86,48	49,00	1,18	1,325	64,925	
11/49	88,20	87,02	86,56	51,00	1,47	1,315	67,065	
12/00	88,00	87,20	86,85	19,00	1,16	1,17	22,23	
12/19	87,86	87,14	86,69	32,00	1,18	1,075	34,4	1273m3 baseins
12/84	87,42	87,42	86,80	16,00	0,97	0,94	15,04	
13/00	87,42	87,42	86,82	28,00	0,91	1,385	38,78	
13/28	87,72	87,61	86,87	25,00	1,86	2,44	61	
13/53	89,36	87,61	86,91	17,00	3,02	2,48	42,16	Roku darbs 13/28-14/00Dzelzsceļš
13/70	88,41	87,55	87,10	30,00	1,94	1,46	43,8	
14/00	87,82	87,58	87,11	100,00	0,98	0,845	84,5	
15/00	87,95	87,55	87,16	100,00	0,71	0,855	85,5	
16/00	88,24	87,58	87,21	100,00	1,00	0,95	95	Roku darbs 18/09-18/73 augstspriegums 1v 110kV
17/00	88,08	87,60	87,26	100,00	0,90	1,12	112	
18/00	88,82	87,65	87,31	9,00	1,34	1,24	11,16	
18/09	88,82	87,70	87,32	64,00	1,14	1,24	79,36	
18/73	89,18	87,96	87,34	27,00	1,34	1,76	47,52	
19/00	88,80	88,00	87,36		2,18			

20/00	88,50	88,02	87,41	100,00	1,60	1,89	189	
21/00	88,81	88,1	87,46	100,00	1,53	1,565	156,5	
21/24	88,87	88,11	87,47	24,00	1,60	1,565	37,56	
								Roku darbs 21/20-22/02-18/73
								augstspriegums 1v
								330kV
22/05	88,80	88,18	87,51	81,00	1,91	1,755	142,155	
23/00	89,52	88,28	87,56	95,00	3,07	2,49	236,55	
24/00	89,96	88,41	87,66	100,00	4,53	3,8	380	
24/38	90,50	88,47	87,72	38,00	5,22	4,875	185,25	
				62,00		3,625	224,75	
25/00	89,25	88,57	87,81		2,03			Roku darbs 24/38-25/57 elektrolīnija
25/57	89,69	88,66	87,90	57,00	3	2,515	143,355	
26/00	90,04	88,71	87,97	43,00	3,38	3,19	137,17	
				100,00		3,42	342	
27/00	90,25	88,85	88,12		3,46			
				100,00		3,49	349	
28/00	90,19	88,99	88,27		3,52			
				93,00		3,3	306,9	
28/93	90,37	89,15	88,41		3,08			
				27,00		2,82	76,14	
29/20	90,32	89,20	88,45		2,56			
				80,00		2,485	198,8	
30/00	90,22	89,30	88,58		2,41			
				100,00		2,345	234,5	

[illegible]

43/00	91,21	90,20	89,22	100,00	4,7	4,025	402,5	
44	91,40	90,45	89,42	100,00	4,3	4,5	450	
44/45	91,60	90,50	89,52	45,00	4,17	4,235	190,575	
44/50	91,62	91,62	91,62	5,00	0	2,085	10,425	
							0	

Piezīmes: **7606 m³** grunts transportēšana ar transportu 15km attālumā

grāvis kopā:	13938,49
baseins	1273
grāvis kopā:	15211,49

Piketi	Zemes virsas atzīme m absol.	Pastāvošā dibena atzīme m absol.	Projektētā dibena atzīme m absol.	Astrarums starp piketiēm m	Izrokamais šķērsgrēzums m ²	Vidējais izrokamais šķērsgrēzums m ²	Izrokamā kubatūra m ³	Piezīmes
1	2	3	4	5	6	7	8	9

ÜSİK kods 43193:06

COST RECORDS FOR 2023-2024										
Date	Description	Material Cost	Labor Cost	Overhead Cost	Total Cost	Performance Metrics				
						Efficiency Score	Quality Index	Cost Variance	Profit Margin	
01/00	01/00	90.25	89.55	88.56	88.56	100.00	2.58	2.345	0	
02/00	02/00	92.34	90.11	89.36	89.36	100.00	4.69	5.67	567	
02/77		92.34	90.31	89.66	89.66	77.00	6.65	6.23	479.71	
03/00	03/00	92.31	90.37	89.75	89.75	23.00	5.81	4.52	103.96	
03/54	03/54	92.26	90.50	89.89	89.89	54.00	3.23	3.02	163.08	
04/00	04/00	92.25	90.62	89.95	89.95	46.00	2.81	2.84	130.64	
05/00	05/00	92.05	90.87	90.09	90.09	100.00	2.87	2.88	288	
06/00	06/00	91.75	90.90	90.23	90.23	100.00	2.89	2.595	259.5	
07/00	07/00	91.70	90.91	90.36	90.36	100.00	2.3	2.175	217.5	
						100.00	2.05	1.675	167.5	

Piezīmes: 1430 m³ grunts transportēšana ar transportu 15km attālumā

L. Mihneviča

L. Deinate

Kopā: