

SAMĒRU SARAKSTS

ŪSIK kods 43194:05, ŪSIK kods 43194:03; ŪSIK kods 43194:06

Lapa 1

	Zemes virsas atzīme m absol.	Pastāvošā dibena atzīme m absol.	Projektētā dibena atzīme m absol.	Atstatums starp piketiēm m	Izrokamais šķērsgriezums m2	Vidējais izrokamais šķērsgriezums m2	Izrokamā kubatūra m3	Piezīmes
ŪSIK kods 43194:05								
91,03	90,64	90,03						rokas darbs
91,04	90,65	90,05	16,00	2,38	1,15			120m- 287,9m3
				2,30		18,4		
91,28	90,87	90,12	100,00	3,09	2,695	269,5		
91,53	90,97	90,26	100,00	3,10	3,095	309,5		
92,20	91,12	90,45	100,00		1,55			
				3,57		155		
92,35	91,60	90,71	100,00		1,785			
				3,71		178,5		
93,02	92,12	91,09	100,00		1,855			
				4,85		185,5		
93,47	92,53	91,66	100		3,885			
				2,92		388,5		
93,65	92,85	92,13	100		2,67			
				2,42		267		
94,62	93,42	92,61	100,00		2,825			
				3,23		282,5		
94,30	93,78	93,08	100,00		2,69			
				2,15		269		
94,53	94,00	93,20	100,00		2,38			
				2,61		238		
94,50	93,78	93,28	57,00		1,305			
						74,385		
Kopā:						2635,785		

1318 m3 grunts transportēšana ar transportu 10km attālumā

Piketi	Zemes virsas atzīme m absol.	Pastāvošā dibena atzīme m absol.	Projektētā dibena atzīme m absol.	Atstatums starp piketiēm m	Izrokamais šķērsgriezums m2	Vidējais izrokamais šķērsgriezums m2	Izrokamā kubaturā m3	Piezīmes
1	2	3	4	5,00	6	7	8	9
ŪSIK kods 43194:03								
0/00	93,32	91,96	91,15	100,00	5,09	2,405	240,5	
0/01	93,55	92,05	91,26	100,00	4,81	4,545	454,5	
02/00	93,78	92,23	91,38	100,00	4,28	4,345	434,5	
03/00	93,95	92,30	91,50	100,00	4,41	3,24	324	
04/00	93,85	92,41	91,61	100,00	2,07	4,02	402	
05/00	94,91	92,67	91,80	100,00	5,97	4,575	457,5	
06/00	94,50	92,81	92,08	100,00	3,18	3,2	320	
07/00	94,60	93,04	92,21	100,00	3,22	3,43	343	
08/00	94,53	93,18	92,34	100,00	3,64	3,64	364	rokas darbs 64m- 233m3
09/00	94,79	93,22	92,47	100,00	3,64	3,37	337	rokas darbs
10/00	94,60	93,33	92,60	100,00	3,1	3,505	350,5	79m- 277m3
11/00	94,80	93,48	92,66	100	3,91	4,26	426	
12/00	95,17	93,70	92,73	100	4,61	4,305	430,5	
13/00	94,87	93,75	92,80	100	4,00	4,13	413	
14/00	95,59	93,86	92,87	100	4,26	3,455	345,5	
15/00	95,17	93,62	92,93	100	2,65	3,405	340,5	
16/00	95,58	93,74	93,00	100	4,16	3,77	377	
17/00	95,65	94,00	93,30	100	3,38	3,1	310	
18/00	95,47	94,51	93,82	42,00	2,82	4,58	192,36	
18/42	96,03	94,92	94,04		6,34		6862,36	
Kopā:							6862,36	

Piezīmes: 3431 m3 grunts transportēšana ar transportu 10km attālumā

Piketi	Zemes virsas atzīme m absol.	Pastāvošā dibena atzīme m absol.	Projektētā dibena atzīme m absol.	Atstatums starp piketi m	Izrokamais šķērsgriezums m2	Vidējais izrokamais šķērsgriezums m2	Izrokamā kubatūra m3	Piezīmes
1	2	3	4	5,00	6	7	8	9
ŪSIK kods 43194:06								
0/00	92,9	91,4	90,6	100,00	4,39	4,06	406	
0/01	92,73	91,68	90,72	100,00	3,73	3,9	390	
02/00	93,24	91,73	90,85	100,00	4,07	3,77	377	
03/00	93,44	91,90	91,06	100,00	3,47	4,545	454,5	
04/00	93,35	92,15	91,37	100,00	5,62	4,26	426	
05/00	93,44	92,41	91,68	100,00	2,9	2,29	229	
06/00	93,22	92,61	91,98	100,00	1,68	2,675	267,5	
07/00	94,31	93,00	92,24	100,00	3,67	2,86	286	
08/00	93,82	93,18	92,59	78,00	2,05	2,07	161,46	
08/78	94,37	93,25	92,66		2,09			
Kopā:							2997,46	

Piezīmes: 1499 m3 grunts transportēšana ar transportu 10km attālumā

Aprēķināja

L. Mihņeviča

Pārbaudīja

L. Deinate

